



## 2x MET MASTS (2017)

<b>VESSEL TYPE</b>	Meteorological masts
<b>LOCATION</b>	Doggerbank, UK
<b>PROJECT</b>	Reverse installation of lattice towers and suction bucket



Ardent were awarded the contract to remove 2x Met Masts in the Doggerbank, UK on a Title Transfer contractual basis. The operations conducted from Heavy Lift Jack-Up Accommodation Vessel “Seafox 5”. Ardent designed and fabricated a smart pump interface for controlled connection to existing mono bucket valves and entering space to pressurize mono bucket to free met mast foundation. Ardent took ownership of the Met Masts offshore. Scope of Work: Project Management; Engineering and Design; Provision of Survey Vessel / Jack-Up HLV by Seafox; Marine Operations: Pre-decom survey / Removal ops / Transport; and Disposal based on the circular economy principles..

